



Save 61 % total

Beam:	HEA 400								
Weight:	844 kg								
Number of ADD Parts:	14								
	min.			h/to			SAVE %		
	Assembling Time	Welding Time	Total Time	Assembling h/to	Welding h/to	Total h/to	Assembling %	Welding %	Total %
manually	100 min	120 min	220 min	1,97 h/to	2,37 h/to	4,34 h/to			
SBA Conti	18 min	88 min	106 min	0,36 h/to	1,74 h/to	2,09 h/to	82 %	27 %	52 %
SBA Conti+	18 min	59 min	77 min	0,36 h/to	1,17 h/to	1,53 h/to	82 %	51 %	65 %
SBA2 Conti+	16 min	32 min	48 min	0,32 h/to	0,63 h/to	0,95 h/to	84 %	73 %	78 %
SBA Compact	22 min	88 min	110 min	0,43 h/to	1,74 h/to	2,17 h/to	78 %	27 %	50 %
SBA Compact+	22 min	63 min	85 min	0,43 h/to	1,24 h/to	1,67 h/to	78 %	48 %	61 %
SBA Eco		93 min	93 min		1,84 h/to	1,84 h/to		22 %	58 %
SBA Eco+		68 min	68 min		1,34 h/to	1,34 h/to		43 %	69 %



HEA 400 with 14 add on parts

Structural steel column with crane

Length total: 5920mm

Weight total: 844 kg

